



DEMOLITION WORKS — PROJECT REPORT & QUOTATION

Removal of Floor Tiles to Expose the Structural Ground Slab — Ikeja City Mall

REPORT REFERENCE
RPT-2026-DEMO-001

PREPARED FOR
Broll Properties

DATE
31 July 2026

SITE
Ikeja City Mall, Obafemi
Awolowo Way, Alausa, Ikeja,
Lagos

QUOTATION REF
DFL/QT/2026/DEMO-001

PREPARED BY /
CLASSIFICATION
Dova Futures Limited ·
Confidential

1.0 PROJECT OVERVIEW

This report presents the scope of works, method statement, quantity basis and quotation for the demolition and removal of existing floor tiles at Ikeja City Mall, Ikeja, Lagos, over an area of **5,000 – 5,500 m²**, together with the carting away and lawful disposal of all resulting tiles and rubble. The objective of the works is to strip the existing floor finish and its bedding down to a **clean, exposed structural ground slab**, ready to receive a new finish under a separate package.

The works are executed by mechanical breaking using heavy duty floor scrapers, supported by manual labour for scraping back to the slab, gathering and loading. Debris is removed from site progressively in 20-ton tipper trucks to an approved disposal site. The mall is a live, trading retail environment, so the works proceed bay by bay within the Client's permitted working hours, with tenant access and emergency egress maintained at all times.

IMPORTANT — TO BE PROVIDED BY THE CLIENT

- ✓ **Unobstructed possession of the work area, cleared of stock, fittings and tenant property before each phase commences.**
- ✓ **Mall access permits, work-permit approvals and confirmation of permitted working hours for demolition and truck movements.**
- ✓ **Power and water supply at the work area for tools, dust suppression and clean-down.**
- ✓ **Marked-up records of any services (conduits, pipework, drainage) buried within the screed or slab, where such records exist.**
- ✓ **Designated loading bay / truck holding area and route for tipper access and egress.**

1.1 KEY QUANTITIES

PARAMETER	VALUE
Floor area to be demolished	5,000 – 5,500 m ²
Assumed removal depth (tile + bedding / screed)	≈ 43 – 50 mm
Solid volume of arisings	≈ 215 – 275 m ³
Loose (bulked) volume — bulking factor ≈ 1.4	≈ 301 – 385 m ³
Haulage unit	20-ton tipper (≈ 12 m ³ effective)
Estimated disposal trips	25 – 32 Nos
Disposal trips priced (Section 4.0)	30 Nos

All areas and depths are taken from the client brief and preliminary assessment, and are subject to on-site verification and joint measurement before commencement.

2.0 SCOPE OF WORKS

- **Demolition:** mechanical breaking and removal of existing floor tiles and their bedding / screed over 5,000 – 5,500 m², using heavy duty floor scrapers.
- **Scraping to slab:** manual scraping and chipping back of residual bedding and adhesive to leave a clean, exposed structural ground slab.
- **Gathering & loading:** collection of arisings into stockpiles at the designated loading point and loading into tippers.
- **Carting away:** haulage of all tiles and rubble off site in 20-ton tipper trucks, and lawful tipping at an approved disposal site.
- **Clean-down:** sweeping and clearing of the exposed slab and the access routes used, on completion of each phase.

2.1 METHOD STATEMENT — HOW THE WORK WILL BE DONE

#	STAGE	METHOD
1	Set-up & protection	Area handed over and isolated; hoarding / dust screens erected to shopfronts and circulation routes; protection to lifts, escalators, service risers and drainage outlets; signage and safe walking routes established.
2	Mechanical breaking	Heavy duty floor scrapers break the tile and bedding in controlled bays, working away from the exit route so completed areas are not re-trafficked.
3	Manual scraping to slab	Manual labour follows the breakers, scraping and chipping residual bedding and adhesive back to the structural slab, and gathering arisings for disposal.
4	Loading & haulage	Arisings are wheeled to the designated loading bay and loaded into 20-ton tippers; each load is ticketed and hauled to an approved disposal site.
5	Clean-down & inspection	Exposed slab swept clean; the bay is jointly inspected and signed off with the Client's representative before the next bay opens.

Works proceed bay by bay so that the mall's operations, tenant access and emergency egress routes are maintained at all times.

3.0 SECTION A — DEMOLITION & TILE REMOVAL

DESCRIPTION	QTY	UNIT	RATE (₹)	AMOUNT (₹)
Removal of existing floor tiles and bedding / screed to expose the structural ground slab, including scraping back to slab and gathering of arisings for disposal — floor area 5,000 – 5,500 m²	1	Lump Sum	3,600,000	3,600,000
Section A Subtotal — Demolition				3,600,000

A **lump sum** covering plant, consumables, labour and supervision. Not remeasured within 5,000 – 5,500 m²; area beyond 5,500 m² is a **variation**, priced separately before that work proceeds.

4.0 SECTION B — CARTING AWAY & DISPOSAL

Debris volume is derived from the treated area and the removal depth, allowing for the bulking that occurs when a bonded floor finish is broken up. This is what sets the number of tipper trips. Each 20-ton tipper carries approximately 12 m³ of loose arisings — a load of about 18 tonnes, within the vehicle's payload — so the trip count is governed by the volume of the body rather than by weight.

REMOVAL DEPTH (TILE + BEDDING)	TRIPS AT 5,000 M²	TRIPS AT 5,500 M²
43 mm	≈ 25	≈ 28
45 mm	≈ 26	≈ 29
50 mm	≈ 29	≈ 32

Across the full area and depth range this gives **25 – 32 trips**. Section B is priced on **30 trips** and is **remeasured against signed trip tickets**: any trip below 30 is refunded to the Client, and **any trip above 30 is charged**, both at ₹105,000 per trip inclusive of VAT (Section 7.0).

DESCRIPTION	QTY	UNIT	RATE (₹)	AMOUNT (₹)
Carting away and lawful disposal of demolished tiles and rubble in 20-ton tipper trucks to an approved disposal site, including loading, haulage and tipping fees (remeasurable — adjusted against signed trip tickets)	30	Trips	100,000	3,000,000
Section B Subtotal — Carting Away (remeasurable)				3,000,000

4.1 CARTING AWAY — ADJUSTMENT SCHEDULE

TRIPS ACTUALLY EXECUTED	CARTING (₦)	WORKS SUBTOTAL (₦)	TOTAL INCL. VAT (₦)	ADJUSTMENT (₦)
25 — thinner bedding, efficient loading	2,500,000	6,100,000	6,405,000	– 525,000
26	2,600,000	6,200,000	6,510,000	– 420,000
28	2,800,000	6,400,000	6,720,000	– 210,000
30 — quoted basis	3,000,000	6,600,000	6,930,000	—
31	3,100,000	6,700,000	7,035,000	+ 105,000
32 — thicker screed at the larger area	3,200,000	6,800,000	7,140,000	+ 210,000

The Contract Sum below is stated on the 30-trip basis. Section B is remeasured against signed trip tickets at **₦105,000 per trip** (₦100,000 plus VAT) — refunded to the Client below 30 trips, and charged to the Client above 30. On the 25 – 32 trip range the final account falls between **₦6,405,000 and ₦7,140,000** inclusive of VAT.

5.0 COST SUMMARY & CONTRACT SUM

DESCRIPTION	AMOUNT (₦)
A — Demolition & Tile Removal (lump sum, 5,000 – 5,500 m²)	3,600,000
B — Carting Away & Disposal (30 trips @ ₦100,000 — remeasurable)	3,000,000
Works Subtotal	6,600,000
VAT (5%)	330,000

CONTRACT SUM	₦ 6,930,000
--------------	-------------

Amount in words: Six Million, Nine Hundred and Thirty Thousand Naira Only.

The Contract Sum is inclusive of VAT at 5%. Section A is a **lump sum** covering any area between 5,000 and 5,500 m² and is not remeasured; Section B is a **remeasurable quantity** and the final account is adjusted up or down against signed trip tickets, as set out in Sections 4.1 and 7.0.

6.0 COMMERCIAL TERMS & EXCLUSIONS

- **Payment schedule:** 60% on mobilisation (~~£~~4,158,000) · 30% on completion of the demolition — all tile and bedding broken out and scraped off the ground (~~£~~2,079,000) · 10% on completion of the whole of the works, clean-down and joint sign-off (~~£~~693,000).
- **Adjustments** arising under Section 7.0 are settled against the final 10% payment — a refund is set off against it, and where the refund exceeds that payment the balance is remitted to the Client within 14 days of the final account; additional trips are added to it and invoiced with the final account.
- **Programme:** approximately 5 – 7 weeks from mobilisation and possession of the area, subject to the Client's confirmed permitted working hours and uninterrupted access. A phased handover of the area will extend this.
- **Quotation validity:** 30 days from the date of this document.
- **Measurement:** Section A is a lump sum and is **not remeasured** within the 5,000 – 5,500 m² range; area beyond 5,500 m² is a variation. Section B is remeasured against signed trip tickets, each countersigned by the Client's representative, and is adjusted in either direction at ~~£~~105,000 per trip inclusive of VAT.
- **Insurance:** Contractor's all-risk and workmen's compensation cover in place for the duration of the works.
- **Excluded — buried services:** scanning / detection is excluded and recommended as a separate item, as is repair of any service struck where no record was provided.
- **Excluded — making good:** repair, levelling, screeding, waterproofing or making good of the exposed structural slab. This quotation covers demolition and removal only.
- **Excluded — structural & fit-out elements:** removal of any part of the structural slab itself, saw-cutting, coring, or breaking out of kerbs, thresholds, plinths or shop fit-out elements, unless separately instructed.

7.0 NOTE — CARTING QUANTITY & REMEASUREMENT

- Section B is priced on **30 trips** and remeasured. The Client is charged for the trips actually executed, each evidenced by a signed trip ticket countersigned by the Client's representative, at **₹105,000 per trip inclusive of VAT**.
- **Below 30 trips the difference is refunded to the Client; above 30 trips it is charged to the Client**, at that same rate. Only trips actually executed and ticketed are billed.
- Section A is likewise a **lump sum** across 5,000 – 5,500 m² and carries no adjustment within that range, in either direction. Only floor area **in excess of 5,500 m²** gives rise to a variation, priced and agreed in writing before that work proceeds.

AUTHORISATION & ACCEPTANCE

By signing below, the Client confirms acceptance of this Report & Quotation and authorises DOVA Futures Limited to proceed with the works described, at the Contract Sum of ~~₹~~₹6,930,000 (inclusive of VAT at 5%), subject to remeasurement of the carting-away quantity in accordance with Sections 4.1 and 7.0.

PREPARED BY
Vollmann Akarakiri, Principal

DATE: 31 Jul 2026

CLIENT ACCEPTANCE
[Client Name & Title]

DATE: *[Date]*