



DEMOLITION WORKS — PROJECT REPORT & QUOTATION

Removal of Floor Tiles to Expose the Structural Ground Slab — Ikeja City Mall

REPORT REFERENCE
RPT-2026-DEMO-001

PREPARED FOR
Broll Properties
[Contact Name & Title]

DATE
31 July 2026

SITE
Ikeja City Mall, Obafemi Awolowo
Way, Alausa, Ikeja, Lagos

QUOTATION REF
DFL/QT/2026/DEMO-001

PREPARED BY /
CLASSIFICATION
Dova Futures Limited · Confidential

1.0 PROJECT OVERVIEW

This report presents the scope of works, method statement, quantity basis and quotation for the demolition and removal of existing floor tiles at Ikeja City Mall, Ikeja, Lagos, over an area of approximately **5,000 m²**, together with the carting away and lawful disposal of all resulting tiles and rubble. The objective of the works is to strip the existing floor finish and its bedding down to a **clean, exposed structural ground slab**, ready to receive a new finish under a separate package.

The works are executed by mechanical breaking using jack hammers and scrapers, supported by manual labour for scraping back to the slab, gathering and loading. Debris is removed from site progressively in 20-ton tipper trucks to an approved disposal site. Because the mall is a live, trading retail environment, the programme, working hours and protection measures set out in Section 6.0 are integral to this quotation.

IMPORTANT — TO BE PROVIDED BY THE CLIENT

- ✓ **Unobstructed possession of the work area, cleared of stock, fittings and tenant property before each phase commences.**
- ✓ **Mall access permits, work-permit approvals and confirmation of permitted working hours for demolition and truck movements.**
- ✓ **Power and water supply at the work area for tools, dust suppression and clean-down.**
- ✓ **Marked-up records of any services (conduits, pipework, drainage) buried within the screed or slab, where such records exist.**
- ✓ **Designated loading bay / truck holding area and route for tipper access and egress.**

1.1 EXISTING CONDITION & EXTENT

- Existing finish: floor tiles laid on a cement sand bedding / screed over the structural ground slab.
- Required end state: bedding and screed removed in full so that the structural ground slab is exposed, swept clean and free of loose material.
- Area to be treated: approximately 5,000 m², to be confirmed by joint measurement on site before commencement.
- Setting: an operating shopping mall — works are subject to noise, dust, vibration and access controls (Section 6.0).

1.2 KEY QUANTITIES

PARAMETER	VALUE
Floor area to be demolished	≈ 5,000 m²
Assumed removal depth (tile + bedding / screed)	≈ 43 – 50 mm
Solid volume of arisings	≈ 215 – 250 m³
Loose (bulked) volume — bulking factor ≈ 1.4	≈ 301 – 350 m³
Haulage unit	20-ton tipper (≈ 12 m³ effective)
Estimated disposal trips	25 – 30 Nos

All areas and depths are taken from the client brief and preliminary assessment, and are subject to on-site verification and joint measurement before commencement.

2.0 SCOPE OF WORKS

- **Demolition:** mechanical breaking and removal of existing floor tiles and their bedding / screed over approximately 5,000 m², using jack hammers and scrapers.
- **Scraping to slab:** manual scraping and chipping back of residual bedding and adhesive to leave a clean, exposed structural ground slab.
- **Gathering & loading:** collection of arisings into stockpiles at the designated loading point and loading into tippers.
- **Carting away:** haulage of all tiles and rubble off site in 20-ton tipper trucks, and lawful tipping at an approved disposal site.
- **Clean-down:** sweeping and clearing of the exposed slab and the access routes used, on completion of each phase.

2.1 METHOD STATEMENT — HOW THE WORK WILL BE DONE

#	STAGE	METHOD
1	Set-up & protection	Area handed over and isolated; hoarding / dust screens erected to shopfronts and circulation routes; protection to lifts, escalators, service risers and drainage outlets; signage and safe walking routes established.
2	Trial strip	A small trial area is stripped first to confirm the actual tile and bedding thickness, the bond to the slab, and the presence of any buried services — the result governs the confirmed trip forecast under Section 4.0.
3	Mechanical breaking	Jack hammers and floor scrapers break the tile and bedding in controlled bays, working away from the exit route so completed areas are not re-trafficked.
4	Manual scraping to slab	Manual labour follows the breakers, scraping and chipping residual bedding and adhesive back to the structural slab, and gathering arisings for disposal.
5	Loading & haulage	Arisings are wheeled to the designated loading bay and loaded into 20-ton tippers; each load is ticketed and hauled to an approved disposal site.
6	Clean-down & inspection	Exposed slab swept clean; the bay is jointly inspected and signed off with the Client's representative before the next bay opens.

Works proceed bay by bay so that the mall's operations, tenant access and emergency egress routes are maintained at all times.

3.0 SECTION A — DEMOLITION & TILE REMOVAL

DESCRIPTION	QTY	UNIT	RATE (₹)	AMOUNT (₹)
Demolition and removal of existing floor tiles and bedding / screed to expose the structural ground slab, using jack hammers and scrapers, including manual scraping back to slab and gathering of arisings for disposal	5,000	m²	750	3,750,000
Section A Subtotal — Demolition				3,750,000

The rate of ₹750/m² is all-inclusive of plant (jack hammers, compressors, scrapers), consumables, labour and supervision. The measured area will be reconciled against joint site measurement on completion.

4.0 SECTION B — CARTING AWAY & DISPOSAL

Debris volume is derived from the treated area and the removal depth, allowing for the bulking that occurs when a bonded floor finish is broken up. This is what sets the number of tipper trips. Each 20-ton tipper carries approximately 12 m³ of loose arisings — a load of about 18 tonnes, within the vehicle’s payload — so the trip count is governed by the volume of the body rather than by weight.

REMOVAL DEPTH (TILE + BEDDING)	SOLID VOL. (M³)	LOOSE VOL. @ 1.4 (M³)	TRIPS @ ≈12 M³
43 mm	215	301	≈ 25
45 mm	225	315	≈ 26
50 mm (adopted for pricing)	250	350	≈ 30

This gives a working range of 25 – 30 trips for a 5,000 m² area. Section B is priced at the upper end of that range — 30 trips — so that the Contract Sum is a maximum, not an estimate. Trips are evidenced by signed trip tickets and any trip not executed is refunded (Section 9.0).

DESCRIPTION	QTY	UNIT	RATE (₹)	AMOUNT (₹)
Carting away and lawful disposal of demolished tiles and rubble in 20-ton tipper trucks to an approved disposal site, including loading, haulage and tipping fees (maximum quantity — refundable if fewer trips are executed)	30	Trips	100,000	3,000,000
Section B Subtotal — Carting Away (maximum)				3,000,000

4.1 CARTING AWAY — REFUND SCHEDULE

TRIPS ACTUALLY EXECUTED	CARTING (₹)	WORKS SUBTOTAL (₹)	TOTAL INCL. VAT (₹)	REFUND TO CLIENT (₹)
25 — thinner bedding, efficient loading	2,500,000	6,250,000	6,718,750	537,500
26	2,600,000	6,350,000	6,826,250	430,000
28	2,800,000	6,550,000	7,041,250	215,000
30 — quoted maximum	3,000,000	6,750,000	7,256,250	—

The Contract Sum below is stated on the 30-trip maximum. Every trip not executed is refunded at ₹107,500 (₹100,000 plus VAT), evidenced by signed trip tickets. The final account cannot exceed the Contract Sum — it can only fall.

5.0 COST SUMMARY & CONTRACT SUM

DESCRIPTION	AMOUNT (₦)
A — Demolition & Tile Removal (5,000 m² @ ₦750/m²)	3,750,000
B — Carting Away & Disposal (30 trips @ ₦100,000 — maximum)	3,000,000
Works Subtotal	6,750,000
VAT (7.5%)	506,250
CONTRACT SUM	₦ 7,256,250

Amount in words: Seven Million, Two Hundred and Fifty-Six Thousand, Two Hundred and Fifty Naira Only.

The Contract Sum is inclusive of VAT at 7.5%. Section A is a firm remeasurable rate; Section B is a **maximum quantity** — the Contract Sum is a ceiling and the final account can only fall below it, by refund against trip tickets as set out in Sections 4.1 and 9.0.

6.0 WORKING IN AN OPERATING MALL — KEY CONSIDERATIONS

Ikeja City Mall trades while these works proceed. The following controls are allowed for in the rates and are integral to the programme:

- **Working hours.** Jack-hammer breaking is noisy and transmits vibration to adjoining tenancies. Breaking is therefore programmed for the Client's permitted hours — typically after trading. Confirmation of these hours is required before the programme in Section 8.0 can be fixed.
- **Dust control.** Dust screens and hoarding to shopfronts and circulation routes, water suppression at the breaking face, and covered wheeling routes. Operatives wear respiratory protection appropriate to silica dust.
- **Vibration & adjacent property.** Breaking is kept away from shopfront glazing, tiled feature walls and service risers; a condition record of adjoining finishes is agreed with the Client before work starts.
- **Buried services.** Conduits and pipework are commonly cast into screed. Where records exist they are marked up; where they do not, a scan of the area is recommended (Section 7.0). Any service struck is stopped, isolated and reported before work resumes.
- **Access & egress.** Emergency exits, fire routes and tenant access are kept clear at all times; tipper movements use the designated loading bay within the Client's agreed truck window.
- **Safety.** Full PPE, tool-box talks, barricading of open bays, and signage. All operatives are covered under the Contractor's workmen's compensation arrangements.

7.0 ASSUMPTIONS & EXCLUSIONS

- Area of 5,000 m² is approximate and taken from the brief; the final account is remeasured against joint site measurement.
- Tile and bedding thickness is assumed at 43 – 50 mm, which sets the 25 – 30 trip range in Section 4.0. Where the bedding proves a heavily bonded topping requiring materially greater breaking effort, the rate in Section A is subject to review; the trip count in Section B is capped and carries no upward adjustment (Section 9.0).
- The rates assume the Client's permitted working hours allow continuous working within each shift. Extended stop-start restrictions, or a requirement to work in short isolated windows, will require a programme and cost review.
- Scanning / detection of buried services is **excluded** and recommended as a separate item. Repair of services struck where no record was provided is excluded.
- Repair, levelling, screeding, waterproofing or making good of the exposed structural slab is **excluded** — this quotation covers demolition and removal only.
- Removal of any part of the structural slab itself, saw-cutting, coring, or breaking out of kerbs, thresholds, plinths or shop fit-out elements is excluded unless separately instructed.
- Hazardous materials are not anticipated; should any be encountered, work stops and their handling and disposal are treated as a separate instructed item.
- Statutory permits, mall access fees and tenant compensation (if any) are to the Client's account.
- Disposal is to an approved site; abnormal tipping levies imposed after the date of this quotation are recoverable at cost.

8.0 COMMERCIAL TERMS

- **Payment schedule:** 60% on mobilisation (~~£~~4,353,750) · 30% when 70% of the works are complete (~~£~~2,176,875) · 10% on completion, clean-down and joint sign-off (~~£~~725,625).
- **The 70% milestone** is reached when **3,500 m² of the 5,000 m²** has been stripped to exposed structural slab, confirmed by joint site measurement and countersigned by the Client's representative.
- **Refunds** arising under Section 9.0 are set off against the final 10% payment, and where the refund exceeds that payment the balance is remitted to the Client within 14 days of the final account.
- **Programme:** approximately 5 – 7 weeks from mobilisation and possession of the area, subject to the Client's confirmed permitted working hours and uninterrupted access. A phased handover of the area will extend this.
- **Quotation validity:** 30 days from the date of this document.
- **Measurement:** Section A is remeasured on the actual area treated; Section B is refunded down against signed trip tickets, each countersigned by the Client's representative, and is not adjustable upwards.
- **Insurance:** Contractor's all-risk and workmen's compensation cover in place for the duration of the works.

9.0 NOTE — CAPPED CARTING QUANTITY & REFUND

- The **carting-away trip count cannot be fixed before the floor is opened** — the true bedding thickness and the bulking of the arisings are only known once breaking begins.
- Rather than carry this as an open provisional sum, Section B is priced at the **maximum of 30 trips**. The Client is charged only for trips actually executed, each evidenced by a signed trip ticket, and **every trip not executed is refunded at ₦107,500 inclusive of VAT**.
- The trial strip described in Section 2.1 will be carried out in the first days on site, and a **confirmed trip forecast** issued to the Client before bulk removal proceeds.
- The Contract Sum of **₦7,256,250** is therefore a **ceiling**. On the 25 – 30 trip range the final account falls between **₦6,718,750 and ₦7,256,250** inclusive of VAT (Section 4.1). It cannot rise above the Contract Sum.
- Should the bedding prove materially thicker than the 43 – 50 mm assumed — taking the requirement beyond 30 trips — the additional trips are **to the Contractor's account** and are not chargeable to the Client.

AUTHORISATION & ACCEPTANCE

By signing below, the Client confirms acceptance of this Report & Quotation and authorises DOVA Futures Limited to proceed with the works described, at the Contract Sum of ₦7,256,250 (inclusive of VAT at 7.5%), subject to refund of any carting-away trips not executed, in accordance with Sections 4.1 and 9.0.

PREPARED BY Vollmann Akarakiri, Principal DATE: <u>31 Jul 2026</u>	REVIEWED BY <i>[Name & Title]</i> DATE: <i>[Date]</i>	CLIENT ACCEPTANCE <i>[Client Name & Title]</i> DATE: <i>[Date]</i>
--	---	--