



DEMOLITION WORKS — PROJECT REPORT & QUOTATION

# Removal of Floor Tiles to Expose the Structural Ground Slab — Ikeja City Mall

REPORT REFERENCE  
**RPT-2026-DEMO-001**

PREPARED FOR  
Broll Properties  
*[Contact Name & Title]*

DATE  
**31 July 2026**

SITE  
Ikeja City Mall, Obafemi Awolowo  
Way, Alausa, Ikeja, Lagos

QUOTATION REF  
**DFL/QT/2026/DEMO-001**

PREPARED BY /  
CLASSIFICATION  
Dova Futures Limited · Confidential

## 1.0 PROJECT OVERVIEW

This report presents the scope of works, method statement, quantity basis and quotation for the demolition and removal of existing floor tiles at Ikeja City Mall, Ikeja, Lagos, over an area of **5,000 – 5,500 m<sup>2</sup>**, together with the carting away and lawful disposal of all resulting tiles and rubble. The objective of the works is to strip the existing floor finish and its bedding down to a **clean, exposed structural ground slab**, ready to receive a new finish under a separate package.

The works are executed by mechanical breaking using jack hammers and scrapers, supported by manual labour for scraping back to the slab, gathering and loading. Debris is removed from site progressively in 20-ton tipper trucks to an approved disposal site. Because the mall is a live, trading retail environment, the programme, working hours and protection measures set out in Section 6.0 are integral to this quotation.

### IMPORTANT — TO BE PROVIDED BY THE CLIENT

- ✓ **Unobstructed possession of the work area, cleared of stock, fittings and tenant property before each phase commences.**
- ✓ **Mall access permits, work-permit approvals and confirmation of permitted working hours for demolition and truck movements.**
- ✓ **Power and water supply at the work area for tools, dust suppression and clean-down.**
- ✓ **Marked-up records of any services (conduits, pipework, drainage) buried within the screed or slab, where such records exist.**
- ✓ **Designated loading bay / truck holding area and route for tipper access and egress.**

### 1.1 EXISTING CONDITION & EXTENT

- Existing finish: floor tiles laid on a cement sand bedding / screed over the structural ground slab.
- Required end state: bedding and screed removed in full so that the structural ground slab is exposed, swept clean and free of loose material.
- Area to be treated: 5,000 – 5,500 m², to be confirmed by joint measurement on site before commencement. Area beyond 5,500 m² is a variation (Section 7.0).
- Setting: an operating shopping mall — works are subject to noise, dust, vibration and access controls (Section 6.0).

### 1.2 KEY QUANTITIES

| PARAMETER                                       | VALUE                             |
|-------------------------------------------------|-----------------------------------|
| Floor area to be demolished                     | 5,000 – 5,500 m²                  |
| Assumed removal depth (tile + bedding / screed) | ≈ 43 – 50 mm                      |
| Solid volume of arisings                        | ≈ 215 – 275 m³                    |
| Loose (bulked) volume — bulking factor ≈ 1.4    | ≈ 301 – 385 m³                    |
| Haulage unit                                    | 20-ton tipper (≈ 12 m³ effective) |
| Estimated disposal trips                        | 25 – 32 Nos                       |
| Disposal trips priced (capped — Section 4.0)    | 30 Nos                            |

All areas and depths are taken from the client brief and preliminary assessment, and are subject to on-site verification and joint measurement before commencement.

### 2.0 SCOPE OF WORKS

- **Demolition:** mechanical breaking and removal of existing floor tiles and their bedding / screed over 5,000 – 5,500 m², using jack hammers and scrapers.
- **Scraping to slab:** manual scraping and chipping back of residual bedding and adhesive to leave a clean, exposed structural ground slab.
- **Gathering & loading:** collection of arisings into stockpiles at the designated loading point and loading into tippers.
- **Carting away:** haulage of all tiles and rubble off site in 20-ton tipper trucks, and lawful tipping at an approved disposal site.
- **Clean-down:** sweeping and clearing of the exposed slab and the access routes used, on completion of each phase.

2.1 METHOD STATEMENT — HOW THE WORK WILL BE DONE

| # | STAGE                   | METHOD                                                                                                                                                                                                                   |
|---|-------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1 | Set-up & protection     | Area handed over and isolated; hoarding / dust screens erected to shopfronts and circulation routes; protection to lifts, escalators, service risers and drainage outlets; signage and safe walking routes established.  |
| 2 | Trial strip             | A small trial area is stripped first to confirm the actual tile and bedding thickness, the bond to the slab, and the presence of any buried services — the result governs the confirmed trip forecast under Section 4.0. |
| 3 | Mechanical breaking     | Jack hammers and floor scrapers break the tile and bedding in controlled bays, working away from the exit route so completed areas are not re-trafficked.                                                                |
| 4 | Manual scraping to slab | Manual labour follows the breakers, scraping and chipping residual bedding and adhesive back to the structural slab, and gathering arisings for disposal.                                                                |
| 5 | Loading & haulage       | Arisings are wheeled to the designated loading bay and loaded into 20-ton tippers; each load is ticketed and hauled to an approved disposal site.                                                                        |
| 6 | Clean-down & inspection | Exposed slab swept clean; the bay is jointly inspected and signed off with the Client's representative before the next bay opens.                                                                                        |

Works proceed bay by bay so that the mall's operations, tenant access and emergency egress routes are maintained at all times.

3.0 SECTION A — DEMOLITION & TILE REMOVAL

| DESCRIPTION                                                                                                                                                                                                                                                             | QTY | UNIT     | RATE (¥)  | AMOUNT (¥) |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|----------|-----------|------------|
| Demolition and removal of existing floor tiles and bedding / screed to expose the structural ground slab, using jack hammers and scrapers, including manual scraping back to slab and gathering of arisings for disposal — over a floor area of <b>5,000 – 5,500 m²</b> | 1   | Lump Sum | 3,600,000 | 3,600,000  |
| Section A Subtotal — Demolition                                                                                                                                                                                                                                         |     |          |           | 3,600,000  |

Section A is a **lump sum**, all-inclusive of plant (jack hammers, compressors, scrapers), consumables, labour and supervision. It is **not remeasured**: the sum covers any floor area between 5,000 and 5,500 m², and is not reduced if the measured area falls at the lower end of that range. Area in excess of 5,500 m² is a **variation** and will be priced separately before that work proceeds (Section 7.0).

4.0 SECTION B — CARTING AWAY & DISPOSAL

Debris volume is derived from the treated area and the removal depth, allowing for the bulking that occurs when a bonded floor finish is broken up. This is what sets the number of tipper trips. Each 20-ton tipper carries approximately 12 m³ of loose arisings — a load of about 18 tonnes, within the vehicle’s payload — so the trip count is governed by the volume of the body rather than by weight.

| REMOVAL DEPTH (TILE + BEDDING) | TRIPS AT 5,000 M² | TRIPS AT 5,500 M² |
|--------------------------------|-------------------|-------------------|
| 43 mm                          | ≈ 25              | ≈ 28              |
| 45 mm                          | ≈ 26              | ≈ 29              |
| 50 mm                          | ≈ 29              | ≈ 32              |

Across the full area and depth range this gives **25 – 32 trips**. Section B is nevertheless priced and **capped at 30 trips**, so that the Contract Sum is a **maximum, not an estimate**. Trips are evidenced by signed trip tickets: any trip below 30 is refunded, and **any trip above 30 is to the Contractor’s account** and is not chargeable to the Client (Section 9.0).

| DESCRIPTION                                                                                                                                                                                                                             | QTY | UNIT  | RATE (₺) | AMOUNT (₺) |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|-------|----------|------------|
| Carting away and lawful disposal of demolished tiles and rubble in 20-ton tipper trucks to an approved disposal site, including loading, haulage and tipping fees<br><i>(maximum quantity — refundable if fewer trips are executed)</i> | 30  | Trips | 100,000  | 3,000,000  |
| Section B Subtotal — Carting Away (maximum)                                                                                                                                                                                             |     |       |          | 3,000,000  |

4.1 CARTING AWAY — REFUND SCHEDULE

| TRIPS ACTUALLY EXECUTED                 | CARTING (₺) | WORKS SUBTOTAL (₺) | TOTAL INCL. VAT (₺) | REFUND TO CLIENT (₺) |
|-----------------------------------------|-------------|--------------------|---------------------|----------------------|
| 25 — thinner bedding, efficient loading | 2,500,000   | 6,100,000          | 6,405,000           | 525,000              |
| 26                                      | 2,600,000   | 6,200,000          | 6,510,000           | 420,000              |
| 28                                      | 2,800,000   | 6,400,000          | 6,720,000           | 210,000              |
| 30 — quoted maximum                     | 3,000,000   | 6,600,000          | 6,930,000           | —                    |

The Contract Sum below is stated on the 30-trip maximum. Every trip not executed is refunded at **₺105,000** (₺100,000 plus VAT), evidenced by signed trip tickets. **The final account cannot exceed the Contract Sum** — it can only fall.

5.0 COST SUMMARY & CONTRACT SUM

| DESCRIPTION                                                 | AMOUNT (₦)  |
|-------------------------------------------------------------|-------------|
| A — Demolition & Tile Removal (lump sum, 5,000 – 5,500 m²)  | 3,600,000   |
| B — Carting Away & Disposal (30 trips @ ₦100,000 — maximum) | 3,000,000   |
| Works Subtotal                                              | 6,600,000   |
| VAT (5%)                                                    | 330,000     |
| CONTRACT SUM                                                | ₦ 6,930,000 |

**Amount in words:** Six Million, Nine Hundred and Thirty Thousand Naira Only.

The Contract Sum is inclusive of VAT at 5%. Section A is a **lump sum** covering any area between 5,000 and 5,500 m² and is not remeasured; Section B is a **maximum quantity**. The Contract Sum is therefore a ceiling and the final account can only fall below it, by refund against trip tickets as set out in Sections 4.1 and 9.0.

6.0 WORKING IN AN OPERATING MALL — KEY CONSIDERATIONS

Ikeja City Mall trades while these works proceed. The following controls are allowed for in the rates and are integral to the programme:

- **Working hours.** Jack-hammer breaking is noisy and transmits vibration to adjoining tenancies. Breaking is therefore programmed for the Client's permitted hours — typically after trading. Confirmation of these hours is required before the programme in Section 8.0 can be fixed.
- **Dust control.** Dust screens and hoarding to shopfronts and circulation routes, water suppression at the breaking face, and covered wheeling routes. Operatives wear respiratory protection appropriate to silica dust.
- **Vibration & adjacent property.** Breaking is kept away from shopfront glazing, tiled feature walls and service risers; a condition record of adjoining finishes is agreed with the Client before work starts.
- **Buried services.** Conduits and pipework are commonly cast into screed. Where records exist they are marked up; where they do not, a scan of the area is recommended (Section 7.0). Any service struck is stopped, isolated and reported before work resumes.
- **Access & egress.** Emergency exits, fire routes and tenant access are kept clear at all times; tipper movements use the designated loading bay within the Client's agreed truck window.
- **Safety.** Full PPE, tool-box talks, barricading of open bays, and signage. All operatives are covered under the Contractor's workmen's compensation arrangements.

## 7.0 ASSUMPTIONS & EXCLUSIONS

---

- The floor area is taken from the brief as **5,000 – 5,500 m<sup>2</sup>** and is confirmed by joint site measurement before commencement. The Section A lump sum covers the whole of that range. Should the measured area **exceed 5,500 m<sup>2</sup>**, the excess is a **variation** — it is measured, priced and agreed in writing before that portion of the work proceeds, and the carting-away cap in Section 4.0 is revisited at the same time.
- Tile and bedding thickness is assumed at 43 – 50 mm, which sets the 25 – 30 trip range in Section 4.0. Where the bedding proves a heavily bonded topping requiring materially greater breaking effort, the rate in Section A is subject to review; the trip count in Section B is capped and carries no upward adjustment (Section 9.0).
- The rates assume the Client's permitted working hours allow continuous working within each shift. Extended stop-start restrictions, or a requirement to work in short isolated windows, will require a programme and cost review.
- Scanning / detection of buried services is **excluded** and recommended as a separate item. Repair of services struck where no record was provided is excluded.
- Repair, levelling, screeding, waterproofing or making good of the exposed structural slab is **excluded** — this quotation covers demolition and removal only.
- Removal of any part of the structural slab itself, saw-cutting, coring, or breaking out of kerbs, thresholds, plinths or shop fit-out elements is excluded unless separately instructed.
- Hazardous materials are not anticipated; should any be encountered, work stops and their handling and disposal are treated as a separate instructed item.
- Statutory permits, mall access fees and tenant compensation (if any) are to the Client's account.
- Disposal is to an approved site; abnormal tipping levies imposed after the date of this quotation are recoverable at cost.

## 8.0 COMMERCIAL TERMS

---

- **Payment schedule:** 60% on mobilisation (~~£~~4,158,000) · 30% when 70% of the works are complete (~~£~~2,079,000) · 10% on completion, clean-down and joint sign-off (~~£~~693,000).
- **The 70% milestone** is reached when **70% of the measured floor area** has been stripped to exposed structural slab — 3,500 m<sup>2</sup> on a 5,000 m<sup>2</sup> floor, 3,850 m<sup>2</sup> on a 5,500 m<sup>2</sup> floor — confirmed by joint site measurement and countersigned by the Client's representative.
- **Refunds** arising under Section 9.0 are set off against the final 10% payment, and where the refund exceeds that payment the balance is remitted to the Client within 14 days of the final account.
- **Programme:** approximately 5 – 7 weeks from mobilisation and possession of the area, subject to the Client's confirmed permitted working hours and uninterrupted access. A phased handover of the area will extend this.
- **Quotation validity:** 30 days from the date of this document.
- **Measurement:** Section A is a lump sum and is **not remeasured** within the 5,000 – 5,500 m<sup>2</sup> range; area beyond 5,500 m<sup>2</sup> is a variation. Section B is refunded down against signed trip tickets, each countersigned by the Client's representative, and is not adjustable upwards.
- **Insurance:** Contractor's all-risk and workmen's compensation cover in place for the duration of the works.

## 9.0 NOTE — CAPPED CARTING QUANTITY & REFUND

- The **carting-away trip count cannot be fixed before the floor is opened** — the true bedding thickness and the bulking of the arisings are only known once breaking begins.
- Rather than carry this as an open provisional sum, Section B is priced at the **maximum of 30 trips**. The Client is charged only for trips actually executed, each evidenced by a signed trip ticket, and **every trip not executed is refunded at ₦105,000 inclusive of VAT**.
- The trial strip described in Section 2.1 will be carried out in the first days on site, and a **confirmed trip forecast** issued to the Client before bulk removal proceeds.
- The Contract Sum of **₦6,930,000** is therefore a **ceiling**. On the 25 – 30 trip range the final account falls between **₦6,405,000 and ₦6,930,000** inclusive of VAT (Section 4.1). It cannot rise above the Contract Sum.
- Where the combination of floor area and bedding thickness takes the requirement **beyond 30 trips** — up to the 32 trips indicated at the top of both ranges in Section 4.0 — the additional trips are **to the Contractor's account** and are not chargeable to the Client.
- Section A is likewise a **lump sum** across 5,000 – 5,500 m<sup>2</sup> and carries no adjustment within that range, in either direction. Only floor area **in excess of 5,500 m<sup>2</sup>** gives rise to a variation, priced and agreed in writing before that work proceeds.

## AUTHORISATION & ACCEPTANCE

By signing below, the Client confirms acceptance of this Report & Quotation and authorises DOVA Futures Limited to proceed with the works described, at the Contract Sum of ₦6,930,000 (inclusive of VAT at 5%), subject to refund of any carting-away trips not executed, in accordance with Sections 4.1 and 9.0.

---

PREPARED BY

Vollmann Akarakiri, Principal

DATE: 31 Jul 2026

---

CLIENT ACCEPTANCE

*[Client Name & Title]*

DATE: *[Date]*