



PROJECT QUOTATION

ROOF LEAKAGE REMEDIAL WORKS — IKEJA CITY MALL

QTE-2026-ICM-ROOF-001

QUOTATION DETAILS

Date: 21 August 2026
Valid Until: 20 September 2026
Prepared By: DOVA Futures Limited — Design Team
Project Ref: ICM-ROOF-001

QUOTED FOR

Broll Properties

Contact person to be confirmed

Ikeja City Mall, Obafemi Awolowo Way, Alausa, Ikeja, Lagos

Phone / email to be confirmed

PROJECT DESCRIPTION

Proposed remedial works for Broll Properties at Ikeja City Mall, based on the visible site inspection recorded in Report RPT-2026-ICM-ROOF-001. Measure 1 addresses the roof-edge coping, blockwork, cracked wall and associated local waterproofing. Measure 2 is a precautionary perimeter treatment limited to approximately 1 metre up the wall and 1 metre onto the slab along an estimated 72-metre perimeter (approximately 144 m²). The main slab area is not included because the existing felt appeared satisfactory during the visible inspection. The exact water-entry path and final extent remain subject to opening-up, cleaning and investigation when work begins.

SCOPE OF WORKS & PRICING

#	DESCRIPTION OF WORKS	UNIT	QTY	RATE (₦)	AMOUNT (₦)
MEASURE 1 — COPING, BLOCKWORK & ASSOCIATED WALL REPAIRS					
1	Bituminous felt	rolls	3	60,000	180,000
2	Labour to felt	m ²	30	1,800	54,000
3	Bituminous primer	drums	1	28,000	28,000
4	Protective aluminium coating	drums	2	32,000	64,000
5	Structural / cracked-wall repair	LS	1	550,000	550,000
6	Roof-cap / coping corrections, fabrication and installation	LS	1	730,000	730,000
Measure 1 subtotal					1,606,000

Measure 2 — precautionary localised perimeter treatment. This allowance covers screeding, Aquaseal admixture, primer and bituminous refelting approximately 1 metre up the wall and 1 metre onto the slab along the estimated 72-metre perimeter (approximately 144 m²). It addresses the slab-to-wall junction and lapping side only; it does not include the full slab area, whose existing felt appeared satisfactory during visible inspection. Protective aluminium coating is excluded. If opening-up reveals a greater treatment extent, DOVA Futures will record it and inform Broll Properties before additional work proceeds.

#	DESCRIPTION OF WORKS	UNIT	QTY	RATE (₦)	AMOUNT (₦)
MEASURE 2 — LOCALISED SLAB-TO-WALL WATERPROOFING					
7	Cement for screeding	bags	50	12,500	625,000
8	Sharp sand — working allowance	tonnes	10	20,000	200,000
9	Aquaseal waterproofing admixture	20-litre keg	1	95,000	95,000
10	Screeding labour	LS	1	350,000	350,000
11	Bituminous felt	rolls	18	60,000	1,080,000
12	Labour to felt	m ²	144	1,800	259,200
13	Bituminous primer	drums	5	28,000	140,000
14	Primer application labour	LS	1	100,000	100,000
15	Protective aluminium coating — excluded from Measure 2	none	0	0	0
Measure 2 subtotal					2,849,200

TERMS & CONDITIONS

- Payment: 60% mobilisation before commencement; 30% after Measure 1 is complete and Measure 2 has commenced with the slab-to-wall perimeter cement screeding completed; and 10% after completion of the entire job.
- Validity: This draft quotation is valid for 30 days from 21 August 2026, subject to confirmation of measurements and client details.
- The exact leakage path, final quantities and repair sequence may change after opening-up, clean-up and site investigation. (This quotation is based on the visible inspection recorded in Report RPT-2026-ICM-ROOF-001.)
- Measure 2 is limited to the perimeter band described above; screeding and refelting of the full slab area are excluded unless later findings are documented and agreed.
- VAT is charged separately at 7.5% after the professional supervision and works charge. All prices are in Nigerian Naira (₦).

Direct works subtotal	₦ 4,455,200
Professional Supervision and Works — 10%	₦ 445,520
VAT — 7.5%	₦ 367,554
GRAND TOTAL	₦ 5,268,274

ACCEPTANCE

FOR DOVA FUTURES LIMITED

Name: _____
Signature: _____
Date: _____

CLIENT ACCEPTANCE — BROLL PROPERTIES

Name: _____
Signature: _____
Date: _____