



PROJECT QUOTATION

ROOF LEAKAGE REMEDIAL WORKS — IKEJA CITY MALL

QTE-2026-ROOF-001

QUOTATION DETAILS

Date: 11 August 2026
Valid Until: 10 September 2026
Prepared By: DOVA Futures Limited — Design-Build Team
Project Ref: BROLL-ROOF-REPAIRS

QUOTED FOR

Broll Properties

Contact person to be confirmed
Ikeja City Mall, Obafemi Awolowo Way, Alausa, Ikeja, Lagos
Phone / email to be confirmed

PROJECT DESCRIPTION

Proposed remedial works for Broll Properties at Ikeja City Mall. The scope is based solely on visible inspection and comprises two measures: Measure 1 — coping, blockwork and associated cracked-wall repairs, including local waterproofing and continuous roof-cap/coping corrections; and Measure 2 — precautionary localised screeding, priming and bituminous refelting at approximately 144 m² of slab-to-wall perimeter. Exact entry point and leakage path remain subject to opening-up and investigation when work begins. Full-roof screeding is excluded.

SCOPE OF WORKS & PRICING

#	DESCRIPTION OF WORKS	UNIT	QTY	RATE (₦)	AMOUNT (₦)
MEASURE 1 — COPING, BLOCKWORK & ASSOCIATED WALL REPAIRS					
1	Bituminous felt	rolls	3	60,000	180,000
2	Labour to felt	m ²	30	1,800	54,000
3	Bituminous primer	drums	1	28,000	28,000
4	Protective aluminium coating	drums	2	32,000	64,000
5	Structural / cracked-wall repair	LS	1	450,000	450,000
6	Roof-cap / coping corrections, fabrication and installation	LS	1	620,000	620,000
Measure 1 subtotal					1,396,000
MEASURE 2 — LOCALISED SLAB-TO-WALL WATERPROOFING					
7	Cement for screeding	bags	50	12,500	625,000
8	Sharp sand — working allowance	tonnes	10	20,000	200,000

#	DESCRIPTION OF WORKS	UNIT	QTY	RATE (₦)	AMOUNT (₦)
10	Screeding labour	LS	1	350,000	350,000
DOVA FUTURES LIMITED QTE-2026-ROOF-001 — Roof Leakage Remedial Works — Ikeja City Mall					
11	Bituminous felt	rolls	18	60,000	1,080,000
12	Labour to felt	m²	144	1,800	259,200
13	Bituminous primer	drums	5	28,000	140,000
14	Primer application labour	LS	1	100,000	100,000
15	Protective aluminium coating — excluded from Measure 2	none	0	0	0
Measure 2 subtotal					2,849,200

TERMS & CONDITIONS

- Payment: payment stages and due dates to be confirmed by the principal after site measurement and quotation acceptance.
- Validity: This draft quotation is valid for 30 days from 11 August 2026, subject to confirmation of measurements, rates and client details.
- Basis: working direct-cost allowances from visible inspection; no overhead, profit or contingency has been added.
- The exact leakage path, final quantities and repair sequence may change after opening-up and site investigation. Full-roof screeding is excluded.
- VAT is shown provisionally at 7.5% and must be confirmed before issue. All prices are in Nigerian Naira (₦).

Subtotal	₦ 4,245,200
VAT (7.5% provisional)	₦ 318,390
GRAND TOTAL	₦ 4,563,590

ACCEPTANCE

By signing below, the client confirms acceptance of this quotation and authorises DOVA Futures Limited to proceed with the works described above.

FOR DOVA FUTURES LIMITED
Pending principal approval

CLIENT ACCEPTANCE
Client acceptance pending