

**DOVA FUTURES**

DESIGNERS · BUILDERS · DEVELOPERS

DOVA FUTURES LIMITED

info@dovafutures.com

+234 816 367 5439

dovafutures.com

SWIMMING POOL — PROJECT REPORT & QUOTATION

Construction of a Swimming Pool for Homework

REPORT REFERENCE

RPT-2026-POOL-002

PREPARED FOR

Homework

DATE

20 July 2026

PREPARED BY

Dova Futures Limited

QUOTATION REF

DFL/QT/2026/POOL-002

CLASSIFICATION

Confidential

1.0 PROJECT OVERVIEW

This report presents the design description, scope of works, preliminary Bill of Quantities (BOQ) and quotation for the construction of a reinforced-concrete swimming pool for Homework. The pool measures 5.4 m × 3.2 m on plan, with a graduated floor from 1.0 m at the shallow end to 1.6 m at the deep end. It is finished in glass mosaic tiles over waterproofed render and serviced by a sand-filter circulation system with underwater lighting. The design incorporates corner entry steps for safe, gradual access, a concrete coping band wrapping the water body with an adjoining paved deck, and a recessed plant niche (powerhouse) housing the filtration and circulation equipment.

IMPORTANT — ITEMS TO BE PROVIDED BY THE CLIENT

- ✓ **All materials for civil works and tiling shall be provided by the Client.**
- ✓ **The Client shall provide water supply up to the powerhouse.**
- ✓ **The Client shall provide electrical power connection up to the powerhouse.**

1.1 DESIGN DESCRIPTION

- Reinforced-concrete pool with corner entry steps for safe, gradual access into the pool.
- Graduated floor sloping from 1.0 m (shallow end) to 1.6 m (deep end).
- Concrete coping band wrapping the water body, with an adjoining paved deck / seating area.
- Recessed plant niche (powerhouse) housing the sand filter and circulation pump, screened within the boundary wall zone.
- Finish: glass mosaic pool tiles over waterproofed render; matt coping and external walkway tiles.

1.2 KEY DIMENSIONS

PARAMETER	VALUE
Pool length (internal)	5,400 mm (5.4 m)
Pool width (internal)	3,200 mm (3.2 m)
Water depth — shallow end	1,000 mm (1.0 m)
Water depth — deep end	1,600 mm (1.6 m)
Average water depth	1,300 mm (1.3 m)
Water surface area	≈ 17.3 m²
Approx. water volume	≈ 22,500 litres (≈ 22.5 m³)
Entry steps	Corner steps (treads TBC)

All dimensions are taken from the client brief and are subject to on-site verification before setting out.

2.0 SCOPE OF WORKS

- **Civil works:** setting out, excavation, blinding, reinforced-concrete pool base and walls, 9" blockwork, rendering and waterproofing.
- **Mechanical works:** supply and installation of sand filter, circulation pump, suction/return pipework, skimmer and main-drain fittings.
- **Electrical works:** underwater pool lights, wiring, conduits, connection to the powerhouse and control-panel installation.
- **Tiling works:** laying of Client-supplied mosaic tiles to pool floor, walls and steps (labour only).

All civil-works materials and tiles are supplied by the Client (Section A). All labour, and the mechanical and electrical packages, are executed by Dova Futures Limited.

3.0 SECTION A — CIVIL WORKS MATERIALS (CLIENT SUPPLY)

DESCRIPTION	QUANTITY
9" Blocks	350 – 500 Nos
Cement	100 – 150 Bags
Marine Boards	25 Sheets
2" × 3" Timber	100 Pieces
Binding Wire	1 Roll
Nails	3 Bags
Waterproofing Liquid (Aquaseal)	2 Kegs
12mm Reinforcement Bars	Approx. 2 Tons
Sharp Sand · Granite · Plaster Sand · Tiles	As Required

Section A materials are Client-supplied and are excluded from the Contract Sum. The Contractor will issue call-off schedules ahead of each stage.

4.0 SECTION B — CIVIL WORKS LABOUR

DESCRIPTION	AMOUNT (₹)
Formwork	200,000
Reinforcement Work	200,000
Masonry Work & Excavation — Blinding, Casting of Base & Walls, Blockwork (Lump Sum)	1,000,000
Civil Works Labour Subtotal	1,400,000

5.0 SECTION C — MECHANICAL WORKS

DESCRIPTION	AMOUNT (₹)
Mechanical Materials (sand filter, circulation pump, pipework & fittings)	2,300,000
Labour Installation	550,000
Mechanical Works Subtotal	2,850,000

6.0 SECTION D — ELECTRICAL WORKS

DESCRIPTION	AMOUNT (₹)
Lighting (underwater pool lights)	400,000
Wiring & Connection to Powerhouse	350,000
Control Panel Connections	350,000
Labour Installation	380,000
Electrical Works Subtotal	1,480,000

7.0 SECTION E — TILING WORKS (LABOUR ONLY)

Tiles are supplied by the Client. The tiled area is computed from the pool dimensions, using an average water depth of 1.3 m.

SURFACE	BASIS	AREA (M²)
Pool floor	5.4 m × 3.2 m	17.28
Pool walls	Perimeter ≈ 17.2 m × 1.3 m avg depth	22.36
Steps (treads & risers)	Lump sum	2.00
Deck area	Lump sum	20.00
Cutting / curvature & coping allowance	Allowance	5.00
Provisional tiled area (for billing)		66.64

DESCRIPTION	AMOUNT (₦)
Labour for Tiling (floor, walls & steps) — Lump Sum	500,000
Tiling Works Subtotal	500,000

Covers installation of mosaic tiles inside the pool, matt grey coping tiles around the pool edge, and matt tiles with wood finishes to the external walkway.

8.0 COST SUMMARY & CONTRACT SUM

DESCRIPTION	AMOUNT (₦)
B — Civil Works Labour	1,400,000
C — Mechanical Works	2,850,000
D — Electrical Works	1,480,000
E — Tiling Labour (Lump Sum)	500,000
Works Subtotal	6,230,000
Contingency Allowance (3%)	186,900
Contractor's Overheads & Profit (10%)	623,000
Subtotal (before VAT)	7,039,900
VAT (7.5%)	527,993

CONTRACT SUM	₦ 7,567,893
--------------	-------------

Amount in words: Seven Million, Five Hundred and Sixty-Seven Thousand, Eight Hundred and Ninety-Three Naira Only.
The Contract Sum is inclusive of VAT at 7.5%. All Client-supply materials (Section A) and tiles are excluded from the Contract Sum.

9.0 ASSUMPTIONS & EXCLUSIONS

- Depth profile taken as 1.0 m → 1.6 m; tiled areas and quantities will be adjusted once depths are confirmed on site.
- All dimensions are from the client brief and are subject to on-site verification before setting out.
- The Client supplies all Section A civil materials and all pool tiles; the Contractor will issue call-off schedules ahead of each stage.
- Water supply up to the powerhouse and electrical power connection up to the powerhouse are provided by the Client, together with site security and unobstructed site access.
- Deck paving/finishes beyond the pool coping band, landscaping and boundary-wall finishes are excluded unless separately instructed.
- Dewatering beyond normal conditions, rock excavation and statutory permit fees (if any) are excluded.

10.0 COMMERCIAL TERMS

- **Payment schedule:** 60% mobilisation · 30% on completion of casting & waterproofing · 10% on completion, testing and handover.
- **Programme:** approximately 6 – 8 weeks from mobilisation, subject to weather and timely material supply.
- **Quotation validity:** 30 days from the date of this document.
- **Workmanship warranty:** 6 months on waterproofing works from the date of handover.

11.0 NOTE — WATERFALL PROVISION

- There is **no provision for a waterfall** in this quotation.
- However, provision can be made for the necessary **waterfall piping during construction** if the Client intends to install a waterfall in the future.
- The inclusion of the waterfall piping shall be at the **Client's discretion** and subject to prior discussion before execution.
- The **supply and installation of the waterfall itself** are not included in this quotation and will only be considered, upon the Client's request, as a **separate item**.

AUTHORISATION & ACCEPTANCE

By signing below, the Client confirms acceptance of this Report & Quotation and authorises DOVA Futures Limited to proceed with the works described, at the Contract Sum of ₦7,567,893 (inclusive of VAT at 7.5%; all Client-supply materials excluded).

PREPARED BY
Vollmann Akarakiri, Principal

DATE: 20 Jul 2026

REVIEWED BY
[Name & Title]

DATE: [Date]

CLIENT ACCEPTANCE
[Client Name & Title]

DATE: [Date]

