



DOVA FUTURES

DESIGNERS · BUILDERS · DEVELOPERS

DOVA FUTURES LIMITED

info@dovafutures.com

+234 816 367 5439

dovafutures.com

DEMOLITION WORKS – PROJECT REPORT & QUOTATION

REMOVAL OF FLOOR TILES TO EXPOSE THE STRUCTURAL GROUND SLAB – IKEJA CITY MALL

REPORT REFERENCE
RPT-2026-DEMO-001

PREPARED FOR
Broll Properties
[Contact Name & Title]

DATE
31 July 2026

SITE
Ikeja City Mall, Obafemi Awolowo
Way, Alausa, Ikeja, Lagos

QUOTATION REF
DFL/QT/2026/DEMO-001

PREPARED BY /
CLASSIFICATION
Dova Futures Limited ·
Confidential

1.0 PROJECT OVERVIEW

This report presents the scope of works, method statement, quantity basis and quotation for the demolition and removal of existing floor tiles at Ikeja City Mall, Ikeja, Lagos, over an area of approximately **5,000 m²**, together with the carting away and lawful disposal of all resulting tiles and rubble. The objective of the works is to strip the existing floor finish and its bedding down to a **clean, exposed structural ground slab**, ready to receive a new finish under a separate package.

The works are executed by mechanical breaking using jack hammers and scrapers, supported by manual labour for scraping back to the slab, gathering and loading. Debris is removed from site progressively in 20-ton tipper trucks to an approved disposal site. Because the mall is a live, trading retail environment, the programme, working hours and protection measures set out in Section 6.0 are integral to this quotation.

IMPORTANT — TO BE PROVIDED BY THE CLIENT

- ✓ Unobstructed possession of the work area, cleared of stock, fittings and tenant property before each phase commences.
- ✓ Mall access permits, work-permit approvals and confirmation of permitted working hours for demolition and truck movements.
- ✓ Power and water supply at the work area for tools, dust suppression and clean-down.
- ✓ Marked-up records of any services (conduits, pipework, drainage) buried within the screed or slab, where such records exist.
- ✓ Designated loading bay / truck holding area and route for tipper access and egress.

1.1 EXISTING CONDITION & EXTENT

- Existing finish: floor tiles laid on a cement sand bedding / screed over the structural ground slab.
- Required end state: bedding and screed removed in full so that the structural ground slab is exposed, swept clean and free of loose material.
- Area to be treated: approximately 5,000 m², to be confirmed by joint measurement on site before commencement.
- Setting: an operating shopping mall — works are subject to noise, dust, vibration and access controls (Section 6.0).

1.2 KEY QUANTITIES

PARAMETER	VALUE
Floor area to be demolished	≈ 5,000 m ²
Assumed removal depth (tile + bedding / screed)	≈ 40 – 50 mm
Solid volume of arisings	≈ 200 – 250 m ³
Loose (bulked) volume — bulking factor ≈ 1.4	≈ 280 – 350 m ³
Haulage unit	20-ton tipper (≈ 12 m ³ effective)
Estimated disposal trips	20 – 30 Nos

All areas and depths are taken from the client brief and preliminary assessment, and are subject to on-site verification and joint measurement before commencement.

2.0 SCOPE OF WORKS

- **Demolition:** mechanical breaking and removal of existing floor tiles and their bedding / screed over approximately 5,000 m², using jack hammers and scrapers.
- **Scraping to slab:** manual scraping and chipping back of residual bedding and adhesive to leave a clean, exposed structural ground slab.
- **Gathering & loading:** collection of arisings into stockpiles at the designated loading point and loading into tippers.
- **Carting away:** haulage of all tiles and rubble off site in 20-ton tipper trucks, and lawful tipping at an approved disposal site.
- **Clean-down:** sweeping and clearing of the exposed slab and the access routes used, on completion of each phase.

2.1 METHOD STATEMENT – HOW THE WORK WILL BE DONE

#	STAGE	METHOD
1	Set-up & protection	Area handed over and isolated; hoarding / dust screens erected to shopfronts and circulation routes; protection to lifts, escalators, service risers and drainage outlets; signage and safe walking routes established.
2	Trial strip	A small trial area is stripped first to confirm the actual tile and bedding thickness, the bond to the slab, and the presence of any buried services — the result governs the remeasured trip count under Section 4.0.
3	Mechanical breaking	Jack hammers and floor scrapers break the tile and bedding in controlled bays, working away from the exit route so completed areas are not re-trafficked.
4	Manual scraping to slab	Manual labour follows the breakers, scraping and chipping residual bedding and adhesive back to the structural slab, and gathering arisings for disposal.
5	Loading & haulage	Arisings are wheeled to the designated loading bay and loaded into 20-ton tippers; each load is ticketed and hauled to an approved disposal site.
6	Clean-down & inspection	Exposed slab swept clean; the bay is jointly inspected and signed off with the Client's representative before the next bay opens.

Works proceed bay by bay so that the mall's operations, tenant access and emergency egress routes are maintained at all times.

3.0 SECTION A – DEMOLITION & TILE REMOVAL

DESCRIPTION	QTY	UNIT	RATE (R)	AMOUNT (R)
Demolition and removal of existing floor tiles and bedding / screed to expose the structural ground slab, using jack hammers and scrapers, including manual scraping back to slab and gathering of arisings for disposal	5,000	m ²	1,800	9,000,000
Section A Subtotal — Demolition				9,000,000

The rate of R1,800/m² is all-inclusive of plant (jack hammers, compressors, scrapers), consumables, labour, supervision, and the Contractor's overheads and profit. The measured area will be reconciled against joint site measurement on completion.

4.0 SECTION B – CARTING AWAY & DISPOSAL

Debris volume is derived from the treated area and the removal depth, allowing for the bulking that occurs when a bonded floor finish is broken up. This is what sets the number of tipper trips, and it is why the trip count is quoted as a band rather than a single fixed figure.

REMOVAL DEPTH (TILE + BEDDING)	SOLID VOL. (M³)	LOOSE VOL. @ 1.4 (M³)	TRIPS @ ≈12 M³
40 mm	200	280	≈ 23
45 mm (adopted for pricing)	225	315	≈ 26
50 mm	250	350	≈ 29

Consistent with the 20 – 30 trip estimate for a 5,000 m² area. Section B is therefore carried as a **provisional quantity of 25 trips** and will be remeasured against signed weighbridge / trip tickets.

DESCRIPTION	QTY	UNIT	RATE (₹)	AMOUNT (₹)
Carting away and lawful disposal of demolished tiles and rubble in 20-ton tipper trucks to an approved disposal site, including loading, haulage and tipping fees (<i>provisional — remeasurable</i>)	25	Trips	280,000	7,000,000
Section B Subtotal — Carting Away (provisional)				7,000,000

4.1 CARTING AWAY – COST SENSITIVITY

SCENARIO	TRIPS	CARTING (₹)	WORKS SUBTOTAL (₹)	TOTAL INCL. VAT (₹)
Lower bound — thinner bedding, efficient loading	20	5,600,000	14,600,000	15,695,000
Adopted basis — quoted Contract Sum	25	7,000,000	16,000,000	17,200,000
Upper bound — thicker screed, higher bulking	30	8,400,000	17,400,000	18,705,000

Only the trips actually executed and evidenced by signed trip tickets will be charged. The Contract Sum below is stated on the 25-trip basis; the final account will move within the band shown.

5.0 COST SUMMARY & CONTRACT SUM

DESCRIPTION	AMOUNT (₦)
A — Demolition & Tile Removal (5,000 m ² @ ₦1,800/m ²)	9,000,000
B — Carting Away & Disposal (25 trips @ ₦280,000 — provisional)	7,000,000
Works Subtotal	16,000,000
VAT (7.5%)	1,200,000
CONTRACT SUM	₦ 17,200,000

Amount in words: Seventeen Million, Two Hundred Thousand Naira Only.

The Contract Sum is inclusive of VAT at 7.5%. Section A is a firm remeasurable rate; Section B is a **provisional quantity** and the final account will be adjusted against trip tickets within the band set out in Section 4.1.

6.0 WORKING IN AN OPERATING MALL — KEY CONSIDERATIONS

Ikeja City Mall trades while these works proceed. The following controls are allowed for in the rates and are integral to the programme:

- **Working hours.** Jack-hammer breaking is noisy and transmits vibration to adjoining tenancies. Breaking is therefore programmed for the Client's permitted hours — typically after trading. Confirmation of these hours is required before the programme in Section 8.0 can be fixed.
- **Dust control.** Dust screens and hoarding to shopfronts and circulation routes, water suppression at the breaking face, and covered wheeling routes. Operatives wear respiratory protection appropriate to silica dust.
- **Vibration & adjacent property.** Breaking is kept away from shopfront glazing, tiled feature walls and service risers; a condition record of adjoining finishes is agreed with the Client before work starts.
- **Buried services.** Conduits and pipework are commonly cast into screed. Where records exist they are marked up; where they do not, a scan of the area is recommended (Section 7.0). Any service struck is stopped, isolated and reported before work resumes.
- **Access & egress.** Emergency exits, fire routes and tenant access are kept clear at all times; tipper movements use the designated loading bay within the Client's agreed truck window.
- **Safety.** Full PPE, tool-box talks, barricading of open bays, and signage. All operatives are covered under the Contractor's workmen's compensation arrangements.

7.0 ASSUMPTIONS & EXCLUSIONS

- Area of 5,000 m² is approximate and taken from the brief; the final account is remeasured against joint site measurement.
- Tile and bedding thickness is assumed at 40 – 50 mm. Where the bedding is materially thicker, or is a heavily bonded topping requiring additional breaking effort, the rate in Section A and the trip count in Section B are subject to review.
- The rates assume the Client's permitted working hours allow continuous working within each shift. Extended stop-start restrictions, or a requirement to work in short isolated windows, will require a programme and cost review.
- Scanning / detection of buried services is **excluded** and recommended as a separate item. Repair of services struck where no record was provided is excluded.
- Repair, levelling, screeding, waterproofing or making good of the exposed structural slab is **excluded** — this quotation covers demolition and removal only.
- Removal of any part of the structural slab itself, saw-cutting, coring, or breaking out of kerbs, thresholds, plinths or shop fit-out elements is excluded unless separately instructed.
- Hazardous materials are not anticipated; should any be encountered, work stops and their handling and disposal are treated as a separate instructed item.
- Statutory permits, mall access fees and tenant compensation (if any) are to the Client's account.
- Disposal is to an approved site; abnormal tipping levies imposed after the date of this quotation are recoverable at cost.

8.0 COMMERCIAL TERMS

- **Payment schedule:** 50% mobilisation · 40% on interim valuation of area completed · 10% on completion, clean-down and joint sign-off.
- **Programme:** approximately 5 – 7 weeks from mobilisation and possession of the area, subject to the Client's confirmed permitted working hours and uninterrupted access. A phased handover of the area will extend this.
- **Quotation validity:** 30 days from the date of this document.
- **Measurement:** Section A is remeasured on the actual area treated; Section B is remeasured on signed trip tickets, each countersigned by the Client's representative.
- **Insurance:** Contractor's all-risk and workmen's compensation cover in place for the duration of the works.

9.0 NOTE – PROVISIONAL QUANTITIES & REMEASUREMENT

- The **carting-away trip count cannot be fixed before the floor is opened** — the true bedding thickness and the bulking of the arisings are only known once breaking begins.
- Section B is therefore carried as a **provisional 25 trips**. The Client is charged only for trips actually executed, each evidenced by a signed trip ticket.
- The trial strip described in Section 2.1 will be carried out in the first days on site, and a **confirmed trip forecast** issued to the Client before bulk removal proceeds.
- On this basis the final account is expected to fall between **£15,695,000 and £18,705,000** inclusive of VAT (Section 4.1), against a quoted Contract Sum of **£17,200,000**.

AUTHORISATION & ACCEPTANCE

By signing below, the Client confirms acceptance of this Report & Quotation and authorises DOVA Futures Limited to proceed with the works described, at the Contract Sum of £17,200,000 (inclusive of VAT at 7.5%), subject to remeasurement of the provisional carting-away quantity in accordance with Sections 4.1 and 9.0.

PREPARED BY Vollmann Akarakiri, Principal	REVIEWED BY [Name & Title]	CLIENT ACCEPTANCE [Client Name & Title]
DATE: 31 Jul 2026	DATE: [Date]	DATE: [Date]